

JAN 18 2001

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa  
(County)

Located In:

Corner Code #

- 1. Public Land Survey { Sec. 1 T 44N R 1W M-1
- Twp. Corner { Sec. 36 T 45N R 1W M-13
- Common to : { Sec. 6 T 44N R 1E A-1
- { Sec. 31 T 45N R 1E A-13
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

94 JUL 22 AM 11:07

*J. Roger Malott*

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Keith R. Waters, in a field survey on OCTOBER 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-1) From 1982 LCRC, L.6, P.217: Found 1" pin in monument box 10' East of the c/l M-129. Accepted corner as found. S77E 58.07' 10" White Spruce Corner is 1' West of East edge of pavement. From MDOT notes 5-01-91: Found boat spike and witnessed prior to road construction with temporary and natural witnesses. S 77 E 57.96' 14" Spruce

1992: Neil Hill found boat spike (Liber 7, Page 366)

- S 77 E 58.09' Found Spike in 14" Spruce
- S 77 E 57.93' MDOT Tag in 14" Spruce
- N 75 W 57.49' MDOT Tag in 7" Poplar
- N 73 E 77.01' MDOT Tag in Power Pole
- N 33 W 132.66' Southeast Corner Concrete Porch

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-1) Found corner and all accessories as recorded in Liber 7, Page 366 of the Chippewa County Records. Accepted corner position as found.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-1) Boat spike in monument box near East Edge of M-129 at East-West Road.

Witnesses:

S 77 E	58.09'	Found Spike in 14" Spruce
S 77 E	57.93'	MDOT Tag in 14" Spruce
N 75 W	57.49'	MDOT Tag in 7" Poplar
N 73 E	77.01'	MDOT Tag in Power Pole
N 33 W	132.66'	Southeast Corner Concrete Porch

Signed by Keith R. Waters

Date 7-22-94

Surveyor's Michigan License No. 33142

NOTE: Bearings are compass bearings corrected for declination.

Distances are to a nail in side of witness objects unless noted.