

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Chippewa Co.

2 Corners.

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> ^{N.} X , R. <u>1</u> X ^{W.}	<u>H-11, G-11</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ ^{N.} S., R. _____ ^{E.} W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} S., R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-23, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-11** Quarter Corner between Sections 27-34, set by James H. Mullett, D.S. in 1845. Bearings were: Maple 10, S1°W, 18 lks. and Sugar 20, N3°E, 30 lks.
- G-11** Section Corner common to Sections 27-28-33-34, set by James H. Mullett, D.S. in 1845. Bearings were: Birch 30, S52°W, 26 lks. and Birch 18, N58°E, 33 lks.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-11** Found 1" pipe driven in Center of Tone Road. Corner is in line with an old fence to North; approx. in line with transmission line to South and is West of road to South.
- G-11** Found 1" pipe driven in intersection of roads.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-11** New Bearings: 12" Red Oak Clump, N15°E, 91.8'.
- G-11** Marked no new witnesses.

SIGNED BY Billy D. Buckler DATE 9-14-78
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____