

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970  
Chippewa Co. 2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. S. R. <u>1</u> W.	<u>H-10</u>
2. PROPERTY CONTROLLING IN SECTION <u>27</u>	, T. <u>45</u> N. S. R. <u>1</u> W.	<u>16-Sec.27</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-7, 19 78, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-10** Center Corner of Section 27.
- 16-Sec.27** East 1/16 Corner on Southside of Section 27.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-10** Corner placed a intersection of lines connecting opposite quarter corners.
- 16-Sec.27** Corner set midway between Section Corner to East and  $\frac{1}{4}$  Corner to West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-10** Placed 1" pipe with 4" aluminium cap at corner.  
Bearings: 10" Oak, S70°E, 19.4' and 8" Oak, N15°E, 26.8' and 6" Oak, S61°W, 9.3'.
- 16-Sec.27** Placed 36" "T" Iron at corner.  
Bearings: 8" Oak Clump, S40°W, 79.5' and 6" Oak Clump, S39°E, 95.85'.  
Corner lies 2.0' South of Center Line of Tone Road.

SIGNED BY Billy D. Buckler DATE 11-14-78  
**Billy D. Buckler**  
 SURVEYOR'S MICHIGAN REGISTRATION NO 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_