

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**  
**Chippewa Co. 4 Corners.**

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	8-Sec.27
2. PROPERTY CONTROLLING IN SECTION <u>27</u>	T. <u>45</u> N. S., R. <u>1</u> E. W.	12-Sec.27
		13-Sec.27
		15-Sec.27
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-7, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- 8-Sec.27 West 1/16 Corner of Section 27.
- 12-Sec.27 South 1/16 Corner of Section 27.
- 13-Sec.27 Southeast 1/16 Corner of Section 27.
- 15-Sec.27 West 1/16 Corner on Southside of Section 27.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**


- 8-Sec.27 Corner placed midway between Center Corner and the West  $\frac{1}{4}$  Corner of Section.
- 12-Sec.27 Placed corner midway between Center Corner to North and  $\frac{1}{4}$  Corner to South.
- 13-Sec.27 Placed corner at center of the Southeast Quarter Section.
- 15-Sec.27 Corner lies in line with fence to North and 24.3' South of fence corner and 8.9' North of center of black top. Distance East and West to nearest corners checks well.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Placed 1" pipe with 4" aluminium cap at all corners except 15-Sec.27.

- 8-Sec.27 Bearings: 12" Maple, S74°E, 29.5' and 6" Oak, N25°E, 33.7' and 14" Oak, S88°W, 17.2'.
- 12-Sec.27 Bearings: 8" Oak, S39°E, 4.7' and 10" Oak, N23°E, 10.5' and 12" Oak, N83°E, 27.1'.
- 13-Sec.27 Bearings: 8" Oak, S59°E, 27.7' and 6" Oak, N15°W, 6.1' and 6" Oak, S30°W, 25.7'.
- 15-Sec.27 Placed 36" "T" Iron at corner. No Bearings.

SIGNED BY Billy D. Buckler DATE 9-14-78  
 Billy D. Buckler  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_