

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 45. NR. 1 West

Chippewa

COUNTY

DESCRIPTION OF CORNER section corner 15-16-21-22

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 6-5-58

10" tamarack S 35°, W 82 links. Marked "S 22 E 1"

12" white birch S 33°, W 32 links. Marked "W 21 E 2"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Re-established section corner by measurements. South 1 mile to section corner. East 1½ miles to 1/4 corner between 14 and 25. Swamp edges to east. Old Makinac trail to west as notes in Brown's Survey in 1809. No evidence of original corner. Corner lies 75 links south of old railroad grade.

SURVEYORS SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 6-17-59  
REGISTERED LAND SURVEYOR