

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T 45 NR 1 West

Chippewa

COUNTY

DESCRIPTION OF CORNER section corner 14 - 15 - 22 - 23

DESCRIPTION OF CORNER MONUMENT 1" size iron brass cap

WITNESSES TO CORNER 6-5-58

1" white pine  $69^{\circ}$ , 1 62 links. marked "14-15"

10" aspen  $77^{\circ}$ , 1 19 links. marked "15-14"

5" balsam  $3^{\circ}$ , 1 54 1/2 links. marked "15-14"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Re-established corner by double proportionate measure from 1/4 corner 1/2 mile east and 1/4 corner 1/2 mile south. Stream crossing 24.00 chains north, old M'Kinac trail to west as noted by Brown's Survey of 1907. Also swamp edges to west. No evidence of original corner. Corner lies 75 links west and 75 links south of old railroad grade. Corner placed and witnessed with H. Bonner, Asst. Forester.

SURVEYORS SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE 6-10-59