

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co. Three Corners.

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> ^{N.} S. , R. <u>1</u> ^{W.} E.	L-7
2. PROPERTY CONTROLLING IN SECTION <u>13</u>	T. <u>45</u> ^{N.} S. , R. <u>1</u> ^{W.} E.	10-Sec.13 11-Sec.13
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. , R. _____ ^{W.} E.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 5-29 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-7 Quarter Cor. bet. Sec's. 13 - 24, set by James H. Mullett, D.S. 1845
Bearings were: Sugar 10", N14°E, 38 lks. and Fir 6", S19°E, 6 lks.
- 10-Sec.13 South 1/16 Corner, on West side Section 13.
- 11-Sec.13 South-West 1/16 Corner, Section 13.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-7 Placed corner 33.0' North of an old fence corner and 10.6' North of center of road. Found position to agree with record by F. H. Brown, County Surveyor 12-6-1913. Corner is nearly midway and is on line with Section corners.
- 10-Sec.13 Placed corner midway bet. $\frac{1}{4}$ Cor. to North and Sec. Cor. to South.
- 11-Sec.13 Placed corner at lines intersecting the South-West quarter section.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminum cap at all corners.

- L-7 New bearings: 13" Hard Maple, N18°E, 58.0' and 20" Y. Birch, N38°W, 84.5'
- 10-Sec.13 Bearings: 16" Hemlock, N70°W, 7.2' and 9" Soft Maple, N42°E, 23.6'
- 11-Sec.13 Bearings: 8" Y. Birch, N °E, 17.5' and 8" Soft Maple, N °W, 7.6'

SIGNED BY Billy D. Buckler

DATE 10-30-74

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____