

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

(County)

Located in:

Corner Code #

- | | | | |
|------------------------------------|------------|--------------------------|----------|
| 1. Public Land Survey | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| 2. Property Controlling in Section | S <u>7</u> | T <u>45N</u> R <u>1W</u> | <u>1</u> |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 16 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (1-Sec. 7) West 1/16 corner between Sections 6 & 7. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

(1-Sec. 7) Established the corner on a line of mean true bearing between Quarter corner 1331.49' east and Section corner 1321.51' west, the position being 20 chains, proportionate to the original record, west of the Quarter corner. From the corner monumented, I found a 2" iron pipe, not of record, N1E (magnetic) 78.1' distant. The centerline of a road is East, 19'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- (1) Set 1"IDx36" Iron pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
- | | |
|------------------------|------------|
| 10" W.Birch N19E 14.7' | "W1/16 BT" |
| 10" W.Birch S35W 4.9' | do |
| 18" W.Birch N72W 43.3' | do |
| 3" Maple N33W 14.1' | do |

Set a cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/18/02

