

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa
 (County)

Located In:	Corner Code #
1. Public Land Survey	T ___ R ___
	T ___ R ___
	T ___ R ___
	T ___ R ___
2. Property Controlling in Section	S <u>7</u> T <u>45N</u> R <u>1W</u> <u>3</u>
	S <u>7</u> T <u>45N</u> R <u>1W</u> <u>4</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___
	S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 16 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (3-Sec. 7) North 1/16 corner between Section 7 T45N-R01W and Section 12 T45N-R02W. Not established in the original survey.
 (4-Sec. 7) Northwest 1/16 corner, Section 7. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(3-Sec. 7) Established the corner midway and on a line of mean true bearing between Quarter corner 1317.44' south and Section corner 1317.44' north.
 (4-Sec. 7) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The center of a N-S road is 23' east of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(3) Set 1"IDx36" Iron pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 20" Y.Birch S64E 34.2' "N1/16 BT" 14" Cedar S29E 26.4' do 14" Cedar S75W 42.3' do 14" Cedar N09E 38.35' do Set a cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 8" Balsam N02W 3.6' "NW1/16 BT" 12" Balsam S25E 13.6' do 6" Maple S80E 37.85' do 5" Balsam S69W 13.35' do Placed a cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/18/02