

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey

T 45N R 1W C3
 T R
 T R
 T R

2. Property Controlling
 in Section

S T R
 S T R

3. Miscellaneous
 Property In Sec.

S T R
 S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

May 16 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3		●										
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(C3) Corner common to Sections 5-6-7-8. 1845: Established by James Mullett D.S.: "North between Sections 7 & 8...80.00 Set post cor. sections 5,6,7,8. Birch 12 S44E 26, Fir 10 N39W 25. 1959: Michigan Dept. of Transportation notes by Ray Walker, Party Chief: "This section corner is a 1 1/2" iron pipe. Found 5-59. 12" spruce 15.10' N12E, 12" spruce 27.52' N56W, 12" spruce 31.36' N75E." 1973: Shown as the POB on recorded plat "Assessor's plat No. 1 of Dafter Twp." by M.D. Alix, RLS 6254 (surveyed in 1970). No description of the monument. Courses to adjacent 1/4 corners south and east as shown as S03 deg. 29' 39" W, 2640.63' and S87 deg. 41' 48"E, 2746.88', respectively.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C3) The original post and accessories were not recovered. Found a 1.5" dia. iron pipe at record distance from the remains of the 1959 NBTs. The spruces N56W and N75E are cut stumps. The spruce N12E is a windthrow. Observed bearings are 12 degrees westerly of the record but form angles consistent with the record. Distances to monumented 1/4 corners south and east were found to be 2639.29' and 2748.54'. The included angle 91 deg. 13' 05" differs from Alix by 01'38". I accept the pipe as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C3) Found 1.5" dia. Iron pipe. Blazed scribed, and set measuring nails in:
 4" Maple S02E 14.35' "S8 NBT"
 5" Maple N77E 19.7' "S5 NBT"
 4" Maple S48E 11.0' "S8 NBT"
 4" W.Birch S43W 19.8' "S7 NBT"
 Bearings are magnetic. Distances are to nail with tag. Placed cedar post adjacent.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/18/02