

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Chippewa  
 (County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                    |                          |           |
|------------------------------------|--------------------------|-----------|
| 1. Public Land Survey              | T <u>45N</u> R <u>1W</u> | <u>85</u> |
|                                    | T _____ R _____          | _____     |
|                                    | T _____ R _____          | _____     |
|                                    | T _____ R _____          | _____     |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____     |
|                                    | S _____ T _____ R _____  | _____     |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____     |
|                                    | S _____ T _____ R _____  | _____     |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jun 12 2002

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(B5) Quarter corner common to Sections 7 and 18. 1845: Established by James Mullett, D.S.: East corrected between 7 & 18... 39.65 Set quarter section post. Tamarac 12 N64W 12, Spruce 6 S25E 12. Undated and unsigned record of MDOT (probably ca. 1959 by Ray Walker, Party Chief) states: Found 3/4" Iron Pipe. 7" Jack Pine 11.07' S80E, 8" Jack Pine 13.67' N05E, 2" Jack Pine 19.73' N43W (Liber 2 Page 232, Chippewa Co. Records).

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(B5) The original post and accessories were not recovered. Found a 3/4" iron pipe in good condition, the top 3" rusted off, at record bearing and distance from the three witnesses of record. The J.Pine witness NE is dead but standing. The remaining two are in good condition. Accepted the monument as the best available evidence of the position of the original corner. The position is 2649.27' West and 2651.03' East of the adjacent Section corners (being 12.53' East of the record position, proportioned) and 3.6' north of a straight line between them.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(B5) Found 3/4" ID iron pipe. Drove a 1" ID x 36" I. pipe with 4" dia. alum. MDNR cap over. Blazed, scribed, and set measuring nails in:  
 4" W.Pine N18E 18.95' "1/4S N8T"  
 7" J.Pine S60W 36.1' do  
 \*7" J.Pine N43W 20.0' do  
 \*10" J.Pine S83E 10.8' do

Bearings are magnetic. Distances are to nail with tag. \* denotes previous witness tree of record.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986



Date 9/18/02