

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey

T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_  
 S 26 T 45N R 1W 8  
 S 26 T 45N R 1W 11

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims

Mar 01 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20 \_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (8-Sec. 26) West 1/16 corner Section 26. Not established in the original survey.
- (11-Sec. 26) Southwest 1/16 corner, Sec. 26. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (8-Sec. 26) Established the corner midway and on a straight line between Quarter corner 1334.88' West and Center of Section 1334.88' East.
- (11-Sec. 26) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |  |
|---|--|
| (8) Set 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>10" Cedar N47W 5.05' mrkd "W1/16 BT"<br>8" Cedar S30W 5.95' do<br>10" Maple S32E 6.75' do<br>12" Cedar N83E 6.65' do<br>Set 6" sq'd and scribed cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (11) Set 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>10" Cedar S02W 6.6' mrkd "SW1/16 BT"<br>8" Cedar S83W 12.55' do<br>6" Cedar N63W 27.85' do<br>16" Hemlock N43W 32.9' do<br>Bearings are magnetic. Distances are to nail with tag. |
|---|--|

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/1/05

For the Michigan Department of Natural Resources, Office of Land and Facilities