

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S 28 T 45N R 1W	9
	S 28 T 45N R 1W	11
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Apr 11 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- (9-Sec. 28) East 1/16 corner Section 28. Not established in the original survey.
  - (11-Sec. 28) Southwest 1/16 corner, Section 28. Not established in the original survey.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- (9-Sec. 28) Established the corner midway and on a straight line between Center of Section 1321.00' West and Quarter corner 1321.00' East.
  - (11-Sec. 28) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- |   |   |
|---|---|
| (9) Set 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>8" Maple S12E 16.2' mrkd "E1/16 BT"<br>14" Y.Birch S87E 12.3' do<br>8" Maple S70W 23.15' do<br>10" Maple N27E 22.95' do<br>Bearings are magnetic. Distances are to nail with tag. | (11) Set 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>12" R.Pine N66W 22.02' mrkd "SW1/16 BT"<br>5" W.Pine S06W 4.1' do<br>10" R.Pine N15W 25.42' do<br>5" W.Pine N40E 22.55' do<br>Bearings are magnetic. Distances are to nail with tag. |
|---|---|

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Stephan J. Szyszkoski Date 6/1/05  
 Surveyor's Michigan License No. 33986