

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S ___ T ___	_____
2. Property Controlling in Section	S <u>28</u> T <u>45N</u> R <u>1W</u>	<u>12</u>
	S <u>21</u> T <u>45N</u> R <u>1W</u>	<u>1/64 S. of E8</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Apr 07 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20 ___ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(12-Sec. 28) South 1/16 corner, Sec. 28. Established in 1997 by Keith Waters PS33142 midway and on a straight line between 1/4 corner to South and Center of Section 10 north. Shown on surveys recorded in Liber 709, Page 557, and Liber 803, Page 359, Chippewa County records.
 (1/64 corner between E8 and the S1/16 corner between Sections 20 and 21). Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(12-Sec. 28) Found a 1/2" dia. iron pin with cap # 33142 set in a concrete cylinder and found it to be midway and on a straight line between 1/4 corner to South and Center of Section to North. Accepted same as a careful and faithful determination of the position of the corner.
 (1/64 South of E8) Found a 1/2" iron pin in a 4" dia. concrete cylinder located substantially at the midpoint and on line between E8 and the monumented S1/16 corner between Sections 20 and 21. Accepted same as a careful and faithful determination of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(12) Fd. 1/2" I.pin with cap #33142 in concrete cylinder. Set measuring nails in:	(1/64 S. of E8) Fd. 1/2" I.pin in conc. cylinder. Set measuring nails in:
4" Oak S74W 20.35' mrkd "S1/16 BT"	18" W.Pine N38E 20.9' mrkd "1/64 BT"
4" W.Birch S25W 32.75' do	12" W.Pine N33W 22.1' do
10" Oak clump S57W 53.5' do	8" Maple S05W 11.3' do
5" W.Pine N23E 7.9' do	6" W.Pine N70W 18.95' do
Bearings are magnetic. Distances are to nail with tag.	Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/1/05

For the Michigan Department of Natural Resources, Office of Land and Facilities