

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S ___ T ___	_____
2. Property Controlling in Section	S <u>21/z8</u> T 45N R 1W	W-W 1/64 21/28
	S 21 T 45N R 1W	15
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	15 Apr 11 2005	
	W-W Apr 07 2005	

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(W-W 1/64 corner between Sections 21 and 28) Being the SE corner of the W1/2 of the SW1/4 of the SW1/4 of Section 21. Not established in the original survey.
 (15-Sec. 21) West 1/16 corner between Sections 21 and 28. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(W-W 1/64) Established the corner on the Section line between Sections 21 and 28 and midway between Sec. corner E9 and the West 1/16 corner between Sections 21 and 28.
 (15-Sec. 21) Established the corner on the Section line and midway between Section corner 1323.67' West and Quarter corner 1323.67' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(W-W 1/64) Set 5/8" x 36" iron pin with plastic cap "MI DNR PS33986". Set measuring nails in:	(15) Set 1" ID x 36" I. pipe with 4" alum. MDNR cap. Set measuring nails in:
10" R. Pine N75E 6.15' mrkd "1/64 BT"	12" R. Pine N12W 1.62' mrkd "W1/16 BT"
10" R. Pine N15E 7.56' do	10" Oak S73W 19.4' do
5" R. Pine N70W 2.82' do	12" R. Pine N79W 16.15' do
10" R. Pine S31W 11.96' do	10" R. Pine N75E 7.4' do
Bearings are magnetic. Distances are to nail with tag.	Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/1/05

For the Michigan Department of Natural Resources, Office of Land and Facilities