

**SURVEY & REMONUMENTATION**

APR 26 1995

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>2W</u>	<u>B-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

\$ 7.00 LAND CORNER  
\$ 2.00 MSSR  
19 DEC 94 10:19 A.M. RECEIPT# 1769  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William L. Karr, in a field survey on November 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B-13) South 1/4 Corner Section 31, T.45 N., R.2 W.  
1840: Wm. Burt set post Fir 10 N27E 16 lks  
Fir 5 N35W 15 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B-13) This corner is being re-established as part of the Chippewa County Remonumentation program.  
Found no evidence of original corner. Found a 1/2" iron w/cap No.24599 at the North 1/4 corner position for Section 6. Re-established the South 1/4 of Section 31, 9.90' West (GLO is 9.90') of the North 1/4 corner. GLO distance for the West 1/2 mile is 2673' (2668.66' today). GLO distance for the East 1/2 mile is 2640' (2639.56' today). There is a 00°42'06" bend on the Township line at this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B-13) Corner is a 3/4"x 24" iron with plastic "Chippewa County Remonumentation" cap, 9.90' West of the North 1/4 corner of Section 6.

Witnesses: 6" Spruce	N12°E 34.97'
P. Pole (E-9)	N85°E 169.23'
"v" notch in end of cap	S29°E 35.43'
P. Pole (E-10)	S33°W 41.69'
8" Aspen	S67°W 78.24'



Signed by William L. Karr

Date 12/08/94

Surveyor's Michigan License No. 27450

723-12

NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted.