

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MAR 27 1996

For corners in

COMMISSION

Chippewa
(County)

Located In:

Corner Code #

1. Public Land Survey

T46N R 2W

D-13 Same

T45N R 2W

D-1 Corner

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

\$ 7.00 LAND CORNER

\$ 2.00 MSSR

29 FEB 96 9:29 A.M. RECEIPT# 462

RECEIVED FOR RECORD

CHIPPEWA COUNTY - STATE OF MICHIGAN

SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Larry R. Rogers, in a field survey on October 23 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(D-13) South 1/4 Corner of Section 32.

1840: Austin Burt "set quarter Section post" with the following witnesses:
14" Spruce N52E 20 links 6" Cedar N43W 19 links

1990: Gerald L. Wiggins, P.S. 23521. Corner recorded in Liber 7, Page 244 of the Chippewa County Corner Records as a "DNR Monument" set midpoint on line between the Southeast and Southwest corners of Section 32 with the following witnesses:

12" Elm S15E 10.1' 4" Maple S72E 14.0'
6" Balsam S58°E 21.3' 6" Spruce N09°E 14.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


(D-13) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found no evidence of original corner position. Found "DNR Monument" and recovered all DNR witnesses. Witnesses check well. Accepted corner position as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D-13) Corner is Michigan D.N.R. stamped aluminum can on a 3/4" iron pipe next to a wood post.

Witnesses: 8" Spruce N08°E 14.67'
6" Maple S75°E 14.07'
8" Balsam S61°E 21.24'
10" Elm S23°E 10.48'



Signed by [Signature]
Surveyor's Michigan License No. 29251

Date 25 DEC 1995

NOTE: All bearings are compass bearings corrected for declination. All distances are to a nail in side of witness objects unless otherwise noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

REVISED OCT., 1985