

SURVEY & REMONUMENTATION

APR 26 1995

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>45N</u> R <u>2W</u> | <u>D-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

\$ 7.00 LAND CORNER
 \$ 2.00 MSSR
 19 JAN 95 4:20 P.M. RECEIPT# 2266
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 REGISTERED DEEDS SECTION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Keith R. Waters in a field survey on December 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13 South 1/4 Corner of Section 32, T45N, R2W.

Original ties to post: Birch 14, N48°E 14 links
 Cedar 8, N25°W 22 links

Found no evidence of subsequent restoration of this corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 (T45N, R2W)

This corner is being re-established as part of the Chippewa County Remonumentation Program.

Found no evidence of corner or its accessories. Re-established corner on line between standard section corners 2633.85 feet east and 2606.55 feet west, on the extension of an old fence line to the north. Corner position falls 16.17 feet west of found remains of a wood post at the north 1/4 corner of Section 5, T44N, R2W, which fits with the computed GLO falling. East-west position also fits well with a fence at the east 1/16 line of Section 32. Corner falls in the approximate centerline of an east-west gravel road (18 Mile Road), and is at approximate split of right-of-way fences 66 feet apart on north and south sides of the road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 (T45N, R2W)

Corner is a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap in the centerline of east-west gravel road (18 Mile Road), on the extension of an old fence line to the north. Witnesses:

- Power Pole (E-10), S82°E 242.57'
- 6" White Pine, S02°E 192.26'
- Power Pole (E-9), S64°W 69.64'
- 3/4" Rebar @ North 1/4 Cor. Sec. 5, EAST 16.17'

Note : Distances to poles and white pine are to a nail and tag in the side. White pine is blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-23-94

Surveyor's Michigan License No. 33142

