

SURVEY & REMONUMENTATION

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner

3/11/98
 11/13/97
 PR: 11/13/97

For corner **SECTION**

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T45N R2W	E-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

\$7.00 LAND CORNER
 \$2.00 MSSR
 6 Mar 1998 1:41:09 PM Receipt #6451
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK **10** PAGE **177**
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


I, Keith R. Waters, in a field survey on November 11, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-6 1/4 Corner common to Sections 16 & 17, Town 45 North, Range 2 West

- 1849 - Original corner (sugar maple post) was established by Harvey Mellen, D.S.
 Witnesses: Lynn 8, S47°E 44 links - Lynn 12, N11°W 35 links
- 1908 - Chippewa County Surveyor Frederick H. Brown notes indicate an original corner.
 Witnesses: Maple 8, N84 1/2°W 21' - Edison Pole, N48 1/2°E 29'
- 1924 - County Surveyor Brown again indicates an original corner, put in monument and post.
- Circa 1930 - County Surveyor corner lie book show the corner as a 24" cement post. Witnesses: Corner of School, N36°W - Maple, N88 1/2°W 21' - Mon., S51°W 28' - Maple 8, S76°E 38' - Pole, N51°E 27' - Maple 5, N31°E 36'
- 1990 - LCRC liber 7, page 307, Gerald L. Wiggins, RLS 23521. Set corner at found iron car spring, this corner was set by County Surveyor in 1924. Placed a 1" pipe with a plastic DNR cap at corner position. Witnesses: 6" Maple, N50°E 17.6' - 12" Maple, N31°E 36.7' - 14" Maple, N20°E 28.2' - 4" Maple, N24°W 24.2'



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
 Found a 1" iron pipe with a plastic DNR cap and all four bearing trees as called for in above mentioned LCRC.
 Accepted corner as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 1" iron pipe with a plastic DNR cap at the corner position, which falls at the approximate centerline P.I. of a curve in Thompson Road to the south and east.
 Witnesses:

- 8" Maple, N45°E 17.72'
- 13" Maple, N26°E 37.10'
- 14" Maple, N16°E 28.81'
- 5" Maple, N26°W 24.20'

Note: Distances are to a nail/tag #33142 in the side of the tree.
 Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters

Date 12-30-97

Surveyor's Michigan License No. 33142

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1985