

SURVEY &
REMONUMENTATION

MAR 09 1994

COMMISSION

Chippewa County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

93 DEC 29 AM 10:26

For corners in

Chippewa
(County)

Located In:

Corner Code ##

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>45N</u> R <u>2W</u> | <u>E-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

J. Roger Malott
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on December 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


A. Description of original monument and accessories and/or subsequent restoration:

- (E-9) Section Corner Common to Sections 20, 21, 28 & 29, (T45N-R2W)
1967 C.E. Wilson; V. Dunbeck. Chippewa County Road Commission. Recorded
 & in Liber 2, Page 189 of the Chippewa County Corner Records. Replaced Cedar
1975 Post and concrete monument with 1" x 18" pipe.
 Face of MBT Post Northeast 41.30' TK in Fence Post Southeast 43.50'
1982 William L. Karr, L.S. 27450. Found 1 1/4" pipe .
 3" Spruce N37°E 91.74'
 Center of Post S42°E 52.50'
 Power Pole DR4/261 S55°W 90.28
 10" Poplar N70°W 120.43'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-9) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found no evidence of the corner. Entire intersection has been raised and paved in road reconstruction. Found three remaining witness objects. Replaced corner using record ties. Added two additional witnesses.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-9) Corner is a 3/4" x 24" iron with plastic "Chippewa County Remonumentation" cap and falls in centerline of Ploegstra Road (East-West, paved) and 1' West of centerline of Nelson Road to North and South.

Witnesses:

- | | | | |
|-------------------------------------|-------|---------|------------------------------------|
| 12" Aspen | N75°W | 120.43' | (existing Fk nail) |
| 6" Spruce | N35°E | 91.74' | (existing Fk nail) |
| Wood Fence Post | S46°E | 52.33' | (existing Post-added nail and tag) |
| "V" Notch in West End of 24" C.M.P. | S30°W | 36.98' | |
| 7" Ash | S52°W | 156.35' | |



Signed by William L. Karr Date 12/15/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.

Distances are to a nail in side of witness objects unless noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983