

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Chippewa County Remonumentation Corner #7.00 LAND CORNER

SECTION

For corners in

| | | |
|------------------------------------|-------------|---------------|
| Chippewa County | Located in: | Corner Code # |
| 1. Public Land Survey | T45N R2W | E-11 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
| 4. Lot No. , Recorded Plat | | |
| 5. Private Claims | | |

\$2.00 MSSR
6 Mar 1998 1:44:17 PM Receipt #6451
RECEIVED FOR RECORD
CHIPPewa COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 181

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on April 11, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-11 Corner common to Sections 28, 29, 32, & 33, T45N, R2W

1849 - Original corner (spruce post) was established by Harvey Mellen, D.S.

Witnesses: Hemlock 14, S07°E 14 links - Fir 10, N74°W 38 links

1908 - Chippewa County Surveyor Frederick H. Brown notes for Section 28 indicate that this corner was established by Kraft (identity unknown). Brown states that Kraft ran the line from his (Brown's) SE corner of Section 28 to the original SW corner of Section 30 and established the SW corner of Section 28 at a distance of 5249 feet from the SE corner of Section 28. The reason for the 5249 foot distance is unknown.

Circa 1930 - Chippewa County Surveyor corner tie book makes two separate references to this corner, both indicating a cement post for the corner position. Numerous witnesses are shown including poles, fence corners, culverts, and trees.

1972 - Liber 3, page 206, Chippewa County corner records. Chippewa County Road Commission section corner record indicates a cedar post and concrete monument at corner position.

Witnesses: Edison Pole, NE 34.80' - Transformer Pole, NW 62.10'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a concrete monument with thin wire at the gravel intersection of 17 Mile Road and Ploegstra Road. Found no evidence of any of the above mentioned witness objects. The distance to section corner A-11 to the west is 10565.0 feet, above mentioned Brown notes show 10565. Distances to section corners A-9 to the north, A-13 to the south, and G-11 to the east are within 1.5 feet, 1.2 feet, and 1.0 feet, respectively, of said Brown notes. Although the reasoning for this position remains unclear, the monument appears to occupy the same position as described by Brown approximately 90 years ago. Accepted corner as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a concrete monument with thin wire at the corner location, which falls in the approximate center of the gravel road intersection of 17 Mile Road and Centerline Road.

Witnesses:

- 32" White Pine, S72°W 192.39'
- Power Pole (RU2-114), N48°W 67.98'
- Power Pole (E30), N37°E 41.11'
- Power Pole (E38), S82°W 272.12'

Note: Distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-30-97

Surveyor's Michigan License No. 33142

