

**SURVEY &
REMONUMENTATION**

APR 07 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner**

For corners in **SECTION**

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T45N R2W	G-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

\$7.00 LAND CORNER
\$2.00 MSSR
6 Mar 1998 1:56:09 PM Receipt #6451
RECEIVED FOR RECORD
CHIPPewa COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 192

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters, in a field survey on November 11, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-12 1/4 Corner common to Sections 33 & 34, Town 45 North, Range 2 West

1849 - Original corner (cedar post) was established by Harvey Mellen, D.S.
Witnesses: Tamarack 8, S22°W 50 links
Yellow Birch 10, N66°W 61 links

Found no evidence of subsequent restoration of this corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being reestablished as part of the Chippewa County Remonumentation Program. Found no evidence of corner. Reestablished corner on line between the section corner G-11 2641.9 feet to the north and the standard corner G-13 on the township line 2648.6 feet to the south, on the extension of the remains of a very old fence line to the east. Corner position falls approximately 10 feet west of the centerline of a north-south gravel road and 13 feet north of a newer fence line to the west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a 1/4" x 24" rebar at the corner location, which falls approximately 10 feet west of the centerline of a north-south gravel road and approximately 13 feet north of a fence line to the west.
Witnesses:

- Power Pole (22), N04°W 167.03'
- Power Pole (355), S34°W 41.46'
- Power Pole (354), N43°E 292.31'
- 5" Spruce, S80°E 75.82'

Note: Distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters

Date 12-30-97

Surveyor's Michigan License No. 33142

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

BOOK 10 PAGE 192