

SURVEY & REMONUMENTATION

CHIPPEWA COUNTY REMONUMENTATION CORNER

APR 26 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Chippewa

(County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 2W	H-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

\$ 7.00 LAND CORNER
 \$ 2.00 HSSR
 19 JAN 95 4:22 P.M. RECEIPT# 2266
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on December 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 H-13 South 1/4 Corner of Section 34, T45N, R2W.
 Original ties to post: Tamarack 14, N30°E 7 links
 Fir 8, N72°W 26 links
 Found no evidence of subsequent restoration of this corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 H-13 (T45N, R2W)
 This corner is being re-established as part of the Chippewa County Remonumentation Program.
 Found no evidence of corner. Re-established corner by single proportionate measurement on the township line mid-way between standard section corners 2637.56 feet east and 2637.56 feet west. Corner is 22.72 feet west of the north 1/4 corner of Section 3, T44N, R2W, and is approximately 1.5 feet south of the centerline of Kallio Road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 H-13 (T45N, R2W)
 Corner is a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap 1.5 feet south of the centerline of Kallio Road. Witnesses:

- 7" Tamarack, S37°E 57.20
- 7" Spruce, N43°E 87.99'
- 7" Balsam Fir, N23°E 78.37'
- Power Pole (RU2-96A-10), N57°W 96.80'
- 3/4" Rebar w/remon. cap @ N.
- 1/4 Cor. Sec. 3, EAST 22.72'

Note: Distances to pole and trees are to a nail and tag in the side. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters
 Surveyor's Michigan License No. 33142

Date 12-23-94

