



APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
 Chippewa County Remonumentation Corner

For corners in **SECTION**

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T45N R2W	K-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

\$7.00 LAND CORNER
 \$2.00 MSSR
 6 Mar 1998 2:05:21 PM Receipt #6451
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 205

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33										
13													

I, Keith R. Waters, in a field survey on November 7, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-9 Corner common to Sections 23, 24, 25, & 26, T45N, R2W

1849 - Original corner (maple post) was established by Harvey Mellen, D.S.

Witnesses: Hemlock 20, N47°E 65 links - Maple 8, S57°W 50 links

Circa 1920 - Chippewa County Surveyor Frederick H. Brown notes for Section 25 indicate "an original corner, stone planted." Brown's notes for Section 23 state "this corner was measured from the corner 24-25 on the town line set stone for corner." Brown's notes for Section 26 read "an original corner or measured west from the original corner 24-25-19-30 on the town line."

1942 - Tone Road plans call for a pointed stone (per LCRC liber 8, page 283).

1959 - Michigan State Highway Department, liber 2, page 232, Chippewa County corner records. Found 1" iron pin.

Witnesses: 4" Maple, S80°W 65.20 - Power Pole, S75°W 37.54'

1959 - Ray Walker, Michigan State Highway Department, liber 2, page 236, Chippewa County corner records.

Found 1 1/2" iron pipe. Witnesses: 4" Maple, S78°W 65.24' - Power Pole, S60°W 37.50'

1974 - LCRC liber 1, page 129, Lawrence Feindt, RLS 21566. Found 1 1/2" iron pipe.

Witnesses: Power Pole, S45°W 40.10' - Steel Post, SOUTH 32.40' - 2" Wild Cherry, N45°E 19.60'

1991 - LCRC liber 8, page 283, Gary E. Koepke, P.S. 26458. Recovered stone and pipe, origin of pipe unknown.

Believe pipe was set to mark location of stone. Accepted stone as corner as it more precisely fits 1942 record. (Witnesses shown in part C)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a pointed stone in a monument box and all witnesses as called for in 1991 LCRC. The stone is most likely the one mentioned in above mentioned Brown notes. Accepted corner as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a pointed stone in a monument box at the corner location, which falls at the approximate centerline extension of Kinross Lake Road to the south, on the south side of the I-75 right of way fence.

Witnesses:

MDOT nail/tag in 8" Cherry, S30°W 38.87'

Nail/tag #3920 in Power Pole (E-12), S50°W 39.51'

MDOT nail/tag in Power Pole (E-12), S50°W 40.02'

Nail/tag #33142 in 3" Aspen, N50°W 11.98' (replaced MDOT nail/tag @ 12.04')

Center of Middle Post of Arrow Sign, S05°W 31.98'

Nail/tag #33142 in 7" Oak, S20°E 105.80' (replaced MDOT nail/tag @ 105.70')



Signed by Keith R. Waters

Date 12-30-97

Surveyor's Michigan License No. 33142