

SURVEY & REMONUMENTATION

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
 Chippewa County Remonumentation Corner

KINROSS TRIP
 PK 11/7/97 ✓

For corners in **SECTION**

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T45 R2W L-7	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

\$7.00 LAND CORNER
 \$2.00 MSSR
 6 Mar 1998 2:07:53 PM Receipt #6451
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON W. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 209

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on June 12, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-7 ¼ Corner common to Sections 13 & 24, Town 45 North, Range 2 West

1849 - Original corner (spruce post) established by Harvey Mellen, D.S.
 Witnesses: Hemlock 12, S11°E 23 links
 Hemlock 14, N25°W 45 links

Found no evidence of subsequent restoration of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being reestablished as part of the Chippewa County Remonumentation Program.
 Found no evidence of corner or its accessories. Reestablished corner by single proportionate measurement midway on line between section corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a ¾" x 48" rebar with a stamped aluminum Chippewa County Remonumentation cap at corner location.
 Witnesses:

- 7" White Pine, S30°W 6.5'
- 12" White Pine, S88°W 30.4'
- 15" Jack Pine, N20°W 32.5'
- 7" Spruce, N60°E 10.5'

Note: Distances are to a nail/tag #33142 in the side of tree.
 Bearings are compass bearings corrected for declination.
 Trees are blazed and painted.

Signed by Keith R. Waters

Date 12-30-97

Surveyor's Michigan License No. 33142

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

