

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Chippewa

(County)

Located in:

Corner Code ##

1. Public Land Survey	T	45NR 2W	D-4
	T	45NR 2W	E-4
	T	45NR 2W	E-5
	T	R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Gerald L. Wiggins, in a field survey on 10-29 & 11-20, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12							
5													
6	15	16	17	18	19	20	21	22	23	24	25	26	27
7													
8	19	20	21	22	23	24							
9													
10	29	30	31	32	33	34	35	36					
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 D-4. Center of Section 8. Not previously set.

E-4 1/4 Corner between 8 and 9. OBT'S: 14" Cedar, N39°W, 21 lks.

E-5 Section Corner common to 8,9,17,16. OBT'S: Cedar 7, S34°E, 13 lks. & Cedar 9, N77°W, 20 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-4 Corner set at intersection of N-S and E-W 1/4 lines of section 8 by closed traverse.

E-4 Found a 3/4" Pipe at corner location.

E-5 Found concrete monument set by county surveyor in 1924.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-4 DNR Monument. 10" Cedar, N40°W, 34.05' & 8" Twin Cedars, N13°W, 14.8' & 6" Twin Cedars, East, 10.0' & 14" W. Birch, S43°E, 14.1'.

E-4 3/4" pipe with plastic RLS Cap. 12" Aspen, N45°W, 32.3' & 12" Spruce, N84°W, 53.5' & 12" Spruce, S67°W, 48.5' & 6" Balsam, N85°W, 44.2'.

E-5 Conc. Monument. 16" Cedar, N75°W, 16.7' & 6" Cedar, S66°E, 10.8' & 6" Cedar, N40°E, 8.4' & 6" Cedar, S52°W, 20.5'.

Signed by

*Gerald L. Wiggins*  
 Gerald L. Wiggins 23521

Date 6-26-91

Surveyor's Michigan License No.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1972

