

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

(County)

Located In:

Corner Code ##

1. Public Land Survey	T	45N	R	2W	D-3
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	5	T	45N R 2W	1
	S	5	T	45N R 2W	D-2
3. Miscellaneous Property in Sec.	S	5	T	45N R 2W	8
	S		T		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gerald L. Wiggins in a field survey on 10-9 & 10-29- 11-20, 19 90 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-3 1/4 Corner between 5 and 8. OBT'S: Cedar 9, N62°W, 22 lks. & Cedar 10, S21°W, 16 lks.

1 West 1/16 corner of north side of section 5. Not previously set.

D-2 Center of Section 5. Not previously set.

8 West 1/16 Corner of Section 5. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-3 Corner set M.P.O.L. between S.W. corner and S.E. corner of section 5.

1 Corner set M.P.O.L. between N.W. corner and north 1/4 corner of section 5.

D-2 Corner set at intersection of E-W and N-S 1/4 lines of sec. 5 by closed traverse.

8 Corner set M.P.O.L. between the west 1/4 corner and the center corner of section 5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 DNR Monument placed at all four corners.

D-3 6" Balsam, N81°W, 75.8' & 6" Balm of Gilead, S38°W, 24.8' & 5" W. Birch, N80°E, 32.1' & 5" W. Birch, N13°E, 31.9'.

1 4" R. Pine, N80°W, 45.1' & 4" R. Pine, S72°E, 22.15' & 4" R. Pine, S65°W, 11.85' & 4" R. Pine, N62°W, 21.8'.

D-2 10" Maple, S22°E, 19.2' & 14" Aspen, S72°E, 33.45' & 8" Spruce, N33°E, 36.9' & 8" Spruce, N03°E, 45.55'.

8 Sq. Post, NE, 0.35' & 12" Aspen, N39°E, 16.7' & 12" Aspen, S80°W, 60.2' & 10" Aspen, N72°W, 57.6'.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8		5		4		3		2		1		
3													
4	7		6		5		4		3		2		1
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by Gerald L. Wiggins
 Surveyor's Michigan License No. 23521

Date 6-26-91

