

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

(County)

Located In:

Corner Code --#

1. Public Land Survey	T	45N	R	2W	I-1
	T	45N	R	2W	J-1
	T	45N	R	2W	C-4
	T	45N	R	2W	C-2
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

I, Gerald L. Wiggins, in a field survey on 9-26 & 10-2, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12							
5													
6	13	14	15	16	17	18	19	20	21	22	23	24	25
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	31	32	33	34	35	36						
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-1 N.W. Sec. Cor. of Sec. 2. OBT'S: Cedar 6, N51°E, 3 lks. & Pine 14, N59°W, 14 lks.

J-1 North 1/4 Cor. of Sec. 2 OBT'S: Spruce 6, N34°E, 22 lks. & Sugar 12, N35°W, 26 lks.

C-4 1/4 Cor. between 7 and 8. OBT'S: Cedar 6, S74°E, 15 lks. & Spruce 10, N62°W, 15 lks.

C-2 1/4 Cor. between 6 and 5. OBT'S: Spruce 8, S65°E, 40 lks. & Spruce 10, S77°W, 38 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 Cor. set M.P.O.L. between Sec. Cors. 1 mile west and 1 mile east, old fence and tree line south, and center of lane North.

J-1 Cor. set M.P.O.L. between N.W. Cor. and N.E. Cor. of Section 2. Line of trees running south.

C-4 Cor. set M.P.O.L. between N.W. Cor. and S.W. Cor. of Section 8.

C-2 Cor. set M.P.O.L. between N.W. Cor. and S.W. Cor. of Section 5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" Pipe with plastic RLS Cap placed at all four corners, pipe is buried east edge of road at C-2.

I-1	Iron Bolt, N30°E, 11.45'	J-1	Center Line of Road, North, 5.6'	C-4	10" Cedar, N56°E, 42.0'
	2" Spruce, N29°E, 62.9'		Power Pole, S45°W, 34.8'		10" Cedar, N89°E, 23.3'
	2" Spruce, N23°W, 61.1'		Sec. Cor. East, 2632.60'		5" Cedar, S40°E, 33.2'
	P. Pole, S50°E, 31.9'		Sec. Cor. West, 2632.60'		8" Cedar, N74°W, 34.5'

C-2 12" Tamarack, N45°E, 24.0' & 14" Tamarack, N67°E, 18.4' & 10" Tamarack, S45°W, 60.8' & 10" Tamarack, N80°W, 41.85'.

Signed by

Gerald L. Wiggins
Gerald L. Wiggins 23521

Date 6-26-91

Surveyor's Michigan License No.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS

