

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa
(County)

	Located In:	Corner Code -#
1. Public Land Survey	T <u>45N</u> R <u>2W</u>	F-3
	T <u>45N</u> R <u>2W</u>	E-6
	T <u>45N</u> R <u>2W</u>	G-4
2. Property Controlling in Section	T _____ R _____	_____
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gerald L. Wiggins, In a field survey on 10-1 & 11-27, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- F-3 1/4 Corner between 4 and 9. OBT'S: Y. Birch 10, S63°E, 5 lks. & Spruce 14, N76°W, 23 lks.
 E-6 1/4 Corner between 17 and 16. OBT'S: Lynn 8, S47°E, 44 lks. & Lynn 12, N11°W, 35 lks.
 G-4 1/4 Corner between 9 and 10. OBT'S: Cedar 10, S65°E, 18 lks. & Cedar 10, N58°W, 22 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-3 Corner set midpoint on line between Northwest Corner and Northeast corner of Section 9.
 E-6 Set Corner at found iron car spring, this corner was set by county surveyor in 1924. Placed our 1" pipe along side of this spring.
 G-4 Corner set midpoint on line between N.E. Corner and S.E. Corner of Section 9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" pipe with plastic RLS Cap at all three corners.

- | | | | | | |
|-----|-------------------------|-----|-------------------------|-----|----------------------------|
| F-3 | 3" Balsam, N65°W, 42.0' | E-6 | 6" Maple, N50°E, 17.6' | G-4 | All with Tags |
| | 5" Apple, N58°W, 40.7' | | 12" Maple, N31°E, 36.7' | | 5" W. Birch, N62°W, 78.5' |
| | 4" Balsam, N15°E, 27.9' | | 14" Maple, N20°E, 28.2' | | 5" W. Birch, N15°E, 102.5' |
| | 8" Aspen, S36°E, 18.3' | | 4" Maple, N24°W, 24.2' | | 5" Aspen, N77°W, 64.7' |
| | | | | | P. Pole, N12°W, 115.5' |

Signed by Gerald L. Wiggins Date 6-26-91
 Surveyor's Michigan License No. 23521

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS

