

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)	Located In:	Corner Code //
1 Public Land Survey	T 45N R 2W	C-1
	T 45N R 2W	C-3
	T 45N R 2W	D-5
	T 45N R 2W	F-5
2 Property Controlling in Section	S T R	
	S T R	
3 Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4 Lot No. , Recorded Plat _____
5 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

Gerald L. Wiggins . . . in a field survey on 5-24 & 6-4 & 6-11 . . . 19 90 . . . do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration:

- C-1 N.W. Section Corner of Sec. 5. ORT'S: Fir 10", N33°E, 17 lks & Fir 7", N29°W, 30 lks.
C-3 S.W. Section Corner of Sec. 5. OBT'S: Spruce 6", N78°E, 7 lks. & Cedar 7", S72°W, 5 lks.
D-5 North 1/4 Corner of Section 17. OBT'S: Tam. 7", N57 1/2°W, 19 lks. & Ced. 7", S37°E, 31 lks.
F-5 South 1/4 Corner of Section 9. OBT'S: Spruce 10", N33°W, 15 lks. & Hemlock 10", South, 39 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-1 Set corner at found iron pin in center line of north and south road.
C-3 Set corner at found iron pin in center line of north and south road.
D-5 Corner set midpoint on line between N.W. Corner and N.E. Corner of Section 17.
F-5 Corner set midpoint on line between S.W. Corner and S.E. Corner of Section 9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


- C-1 1" Pipe with Plastic RLS Cap along side of iron pin. 7" R. Pine, S63°E, 37.7' & 6" Spruce, N42°E, 79.9' & 10" Spruce, N25°W, 71.3' & 8" Spruce, N84°W, 52.3'.
C-3 1" Pipe with Plastic RLS Cap along side of iron pin. 7" Tam., N49°W, 35.7' & 10" Cedar, N55°E, 38.5' & 10" Twin Tam., S56°E, 39.2', & 6" Cedar, S43°W, 42.1'.
D-5 DNR Monument: 5" Spruce, N10°E, 50.0' & 6" Spruce, N78°E, 43.5' & 3" Spruce, S52°E, 15.0' & 3" Tamarack, S4°E, 20.5'.
F-5 DNR Monument: 1" Pipe, S57°W, 12.04' & 4" Maple, N72°W, 20.3' & 6" Cedar, N3°W, 8.3' & 5" Maple, S20°W, 20.3'.

Signed by

Gerald L. Wiggins

Date 9-13-90

Surveyor's Michigan License No. 23521



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN. 1983