

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**Chippewa**  
(County)

	Located In:	Corner Code //
1 Public Land Survey	T 45N R 2W	E-1
	T 45N R 2W	E-3
	T 45N R 2W	D-1
2 Property Controlling in Section	S 5 T 45N R 2W	2
	S T R	
	S T R	
3 Miscellaneous Property in Sec.	S T R	
	S T R	
	S T R	

Register of Deeds Stamp & File Number

4 Lot No. , Recorded Plat \_\_\_\_\_  
 5 Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6	16	17	18	19	20	21	22	23	24	25	26	27	28
7													
8	10	11	12	13	14	15	16	17	18	19	20	21	22
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	11	12	13	14	15	16	17	18	19	20	21	22	23
13													

I, **Gerald L. Wiggins**, in a field survey on 6-13- \_\_\_\_\_, 1990, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A Description of original monument and accessories and/or subsequent restoration:

- E-1 N.E. Section Corner of Section 5. O.B.T.'S: Pine 24" at Corner of Sections 4-5.
- E-3 S.E. Section Corner of Section 5. O.B.T.'S: Cedar 6", S57°E, 21 lks. & Hem. 16", N50°W 34 lks
- D-1 North 1/4 Corner of Section 5. O.B.T.'S.: Spruce 14", N52°E, 20 lks, & Ced. 6", N43°W, 19 lks.
- 2 East 1/16 Corner on North side of Section 5. Not previously set.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner

- E-1 Corner set by single proportionate measure from corners 1 mile east and west. This position fits record distance to stream south and east.
- E-3 Corner set at found iron, two rotten stump bottoms a Cedar and a Hemlock 11e at record distance and bearing from this iron.
- D-1 Corner set midpoint on line between N.W. Corner and N.E. Corner of Section 5. Distance west to stream fits original calls.
- 2 Corner set midpoint on line between North 1/4 Corner and N.E. Corner of Section 5.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-1 DNR Monument: Fence Post, N62°E, 25.3' & Fence Post, S80°E, 21.8' & 4" Elm, S62°E, 69.1' & 10" W. Birch, S35°W, 41.4'
- E-3 DNR Monument: 10" Oak, S2°W, 16.5' & 5" Maple, S39°E, 4.4' & 10" Balsam, N5°E, 6.6' & 4" Maple, S87°E, 15.5'
- D-1 DNR Monument: 12" Elm, S15°E, 10.1' & 6" Balsam, S58°E, 21.3' & 4" Maple, S72°E, 14.0' & 6" Spruce, N9°E, 14.7'
- 2 DNR Monument: 4" Balsam, N22°E, 12.2' & 4" Spruce, N45°E, 27.1' & 10" Aspen, N75°E, 34.0' & 4" Balsam, S62°E, 44.7'.

Signed by Gerald L. Wiggins Date 9-13-90  
 Surveyor's Michigan License No. 23521



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISIONS: FEB. 14, 1976; MAY 14, 1976; REVISED JAN. 1983