

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**CHIPPEWA**

(County)	Located In:	Corner Code #/
1. Public Land Survey	T 45N R 2W	65
	T 45N R 2W	K1
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
6												
8	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on November 26, 1991, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(65) CORNER NOTED IN COUNTY SURVEYORS RECORD BY F.H. BROWN (1908): "HAD ORIGINAL BEARING TREES AND HAVE KEPT POST SINCE BEARING TREES WAS DESTROYED AND PLACED MON'MT AND POST IN 1924". TIES ca. 1924 FROM COUNTY SURVEYOR RECORD ARE AS FOLLOWS: CEMENT POST 24" LONG - N27W 38 MON; S60W 52 BASSWOOD; S27E 52 POLE. CORNER RECORDED BY CHIPPEWA COUNTY ROAD COMMISSION IN 1977 AS FND. COMC. MONUMENT AND REPLACED WITH 1"x18" IRON PIPE IN 1970. CCRC BT'S ARE: TK IN F. POST 30.80' NW; TK IN 8" MAPLE 63.40' SW; TK IN 6" BASSWOOD 81.90' SE; TK IN F. POST 46.30' NE.

(K1) ORIGINAL CORNER ESTABLISHED BY AUSTIN BURT, 1840. CORNER PERPETUATED BY CHIPPEWA COUNTY SURVEYOR F.H. BROWN WHO, IN 1913, STATES THAT HE FOUND 3 ORIGINAL BEARING TREES. SUBSEQUENT RECORDS OF COUNTY SURVEYORS OFFICE (ca. 1913-1930) STATE: CEMENT POST 24" BESIDE PLOW POINT AND STONE BY FORMER SURVEY 1 FOOT BELOW SURFACE. (1) SMALL CEMENT POST N43W 37, (2) POLE N40E 34.5, (3) CEDAR S47 1/2E 40, (4) 25.5'E OF RANGE OF FENCE GOING NORTH FROM NW COR. OF INTERSECTION, (5) 22' E. OF RANGE OF TEL. POLES, (6) N38W 37.5' FENCE CORNER. (7) POST 6.5' EAST OF FENCE COR. IN SE CORNER OF INTERSECTION, (8) 33'W AND 23'S OF FENCE...ON SW OF SEC. 36

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(65) FOUND AND ACCEPTED 1" IRON PIPE 2' WEST OF C/L OF BITUMINOUS PAVEMENT OF BOUND ROAD. CCRC TIE TO 8" MAPLE CHECKS TO A 20" MAPLE WITH OLD SCAR.

(K1) FOUND AND ACCEPTED A CONCRETE MONUMENT WITH A SMALL GAUGE WIRE PROJECTING FROM THE TOP, 12" BELOW GRAVEL ROAD SURFACE. RECORD TIES NOTED CHECKED AS FOLLOWS: (1) NOT FOUND, (2) IN DITCH, NOT FOUND, (3) IN DITCH, NOT FOUND, (4) 29' M, (5) NOT CHECKED, (6) 43' M, (7) IN DITCH, NOT FOUND, (8) FENCE NOT FOUND. PLACED 3/8"x10" FLAGGED SPIKE OVER MONUMENT AND LEFT A MICHIGAN DEPT. OF NATURAL RESOURCES BRASS TAG ADJACENT.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(65) FOUND 1" IRON PIPE. 538E 46.05' SW	(K1) FOUND CONCRETE MONUMENT. 541W
FACE B" FIR; N81E 61.10' NW FACE 10"	40.48' SET NAIL AND MDNR TAG IN NW FACE
MAPLE; S67W 53.37' N. FACE 10" MAPLE;	POWER POLE; S75W 38.7' N. EDGE OF STOP
N70W 83.8' S. FACE 18" WHITE BIRCH.	SIGN; N32W 39.06' SET NAIL AND MDNR TAG
DISTANCES ARE TO NAILS SET IN MDNR TAGS	IN SW FACE POWER POLE; N68E 34.45'
PLACED ON THE FACES NOTED. BEARINGS ARE	CHISELED AND PAINTED A SMALL "+" ON TOP
MAGNETIC AND TO THE CENTER OF THE BT'S.	NORTH END OF CMP.



Signed by Stephan J. Szyszkoski Date 11-27-91  
 Surveyor's Michigan License No. 33986