

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner

SECTION

For corners in

Chippewa County	Located in:	Corner Code #	
1. Public Land Survey	T46N R7W	H-13	Same Corner
	T45N R7W	H-1	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R
4. Lot No.	, Recorded Plat		
5. Private Claims			

BOOK **11** PAGE **107**

\$7.00 LAND CORNER
 \$2.00 NSSR
 23 FEB 2000 4:30:17 PM Receipt #21175
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on January 26, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13 (H-1) 1/4 Corner Common to Section 3, T45N, R7W & Section 34, T46N, R7W

1840 - Original corner established by Austin Burt.
 Witnesses: Spruce 6, N44°E 38 links - Cedar 10, N57°W 40 links.

1963 - Billy D. Buckler, R.L.S. 8887, Michigan Department of Conservation, Forestry Division, Land Corner Record, as recorded in Liber 3, Page 99, Chippewa County Corner Records. Found no evidence of original corner. Reestablished corner midway and on line between section corners. Set a 1" pipe with 4" aluminum cap.
 Witnesses:
 9" Cedar (1/4S NBT), S45°W 53 1/2 links
 8" Cedar (1/4S NBT), N44°W 46 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Found a 1" pipe with a stamped aluminum Department of Conservation cap and both bearing trees as called for in the above mentioned 1963 records. Measurements to adjacent corners confirm the method used in reestablishing the corner. Accepted the corner as found and established additional bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 1" pipe with a stamped aluminum Department of Conservation cap at the corner location.
 Witnesses:
 Nail and tag #33142 in 10" blazed Cedar, S45°W 35.66' (existing bearing tree)
 Nail and tag #33142 in 8" blazed Cedar, N44°W 30.06' (existing bearing tree)
 Nail and tag #33142 in 6" blazed Cedar, N32°E 30.14' (new bearing tree)
 Nail and tag #33142 in 4" blazed Balsam Fir, S56°E 38.37' (new bearing tree)

Signed by Keith R. Waters

Date 12-29-99

Surveyor's Michigan License No. 33142

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995

BOOK **11** PAGE **107**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

