

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Chippewa COUNTY
T 45N R 7W

DESCRIPTION OF CORNER $\frac{1}{4}$ Cor. bet. Secs. 25-26

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8/2/71

WITNESSES TO CORNER..... 6" Cedar ($\frac{1}{4}$ S NBT) N31°W 2.8'



6" W. Birch ($\frac{1}{4}$ S NBT) S63°W 30.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from remains of two probable witnesses; A 30" Cedar stub, bearing N80°E, 11 links and a Tamarack stump bottom, bearing S76°W, 25 links. Found scars on the Cedar but no positive identification. Stub has burned.

Position checks with stream to north and a swamp edge less than a chain to south.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler

DATE 1/10/72

REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68