

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Chippewa COUNTY


T 45N R 7W

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 25-26-35-36

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8/2/71

WITNESSES TO CORNER..... 16" R. Pine (S25 NBT) N76°E 27.3'



5" R. Pine (S36 NBT) S52°E 30.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established at site of and old squared pine stub. Found no evidence of original corner but this location agrees with a  $\frac{1}{4}$  cor.  $\frac{1}{2}$  mile north, with corners to east and with streams to south and west.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Billy D. Buckler*  
Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE

1/7/72

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing