

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

CHIPPewa COUNTY

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>T</u> T. <u>45</u> <u>N</u> R. <u>7</u> <u>W</u>		<u>J-1</u>
2. PROPERTY CONTROLLING IN SECTION _____ .T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ .T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 3-7-70 19 , established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 North Quarter Corner, Section 2, set by Austin Burt, D. S. in 1840.
 Bearings were;
 Sugar 10", N 67° E, 17 Links and Sugar 11", N 41° W, 44 Links.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Found Concrete Monument with a Brass Tablet, set by U. S. General Land Office, 1938.
 Noted a Concrete witness Monument, bearing, N 32° W, 133.9', which has been set more recently. The area is presently being cleared, to increase the sight distance, on the Highway Intersection.
 Found an original witness, N 36° W, 27.5; this tree will be removed

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner re-witnessed to perpetuate position.
 Bearings:
 SW corner of Store Building, N 42° E, 89.3'
 Concrete Witness Monument, N 32° W, 133.9'
 Corner lies 52.5' North of hwy Centerline and 17.1' West of County Road Centerline.

Billy D. Buckler
 Billy D. Buckler

SIGNED BY _____ DATE 12-19-72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8687 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____