

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. <u>7</u> E. <u>W.</u>	J-3
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 12/20 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

$\frac{1}{4}$ Corner bet. Secs., 2-11, set by Wells Curt, D.S. 1850.
Bearings were:
Sugar 8" N58°E 10 lks and Sugar 6" S60°E 16 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner re-established midway and on line bet. two Sec. Cors. Found an erroneous corner location, 210.1' west of this corner. This erroneous corner is in line with road to North. This road has been considered the N.-S. $\frac{1}{4}$ line of Sec. 2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at corner.
New Bearings:
6" Soft Maple N70°E 26.3' and 7" Soft Maple N81°W 21.4'

Placed a 1" x 36" iron pipe at the erroneous corner, 210.1' west of here and noted witnesses to same.
6" Soft Maple S73°E 37.8' and 10" Beech S27°W 14.7'

SIGNED BY Billy D. Buckler DATE 1/4/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____