LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970 Chippewa Co.

FOR CORNERS OF -:	LOCATED IN-:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	_ T S., R W.	6_Sec.7 13_Sec.7	\$6.
2. PROPERTY CONTROLL- 7	,T. 45 N. R. 7 W.		7
3. MISCELLANEOUS PROPERTY IN SECTION			
4. LOT NO, RECO	ORDED PLAT		<u></u>
5. PRIVATE CLAIMS			REGISTER OF DEEDS STAMP AND FILING NUMBER
I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 11/13 19.72, established, re-established, monumented, re-monumented, recovered as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:			
A. Description of original mon 9-Sec.7 East 1/16	ument and accessories and, Corner Sec. 7.	or subsequent restoration:	
·	1/16 Corner, Sec.7.		• • • • • • • • • • • • • • • • • • •
			· 8
B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: 9-Sec. 7 East 1/16 Corner placed midway and on line bot. Center 1 Cor. and East 4 Cor. of Sec. 7. 6-Sec. 7 NE 1/16 Cor. placed at intersection of lines quart-ring the north East Quarter Section.			
13-Sec. 7 SE 1/16 Corner placed at intersection of lines quartering the South Bast quarter section.			
C. Description of monument f Placed 1" pipe with	or corner and accessories 4" aluminium cap at	established to perpetuate loc all three corners.	ating the position of the comer:
9-Sec. 7 Bearings: 7" W. Birch S4°E 58.0' and 7" Spruce N22°E 46.1'			
6-Sec. 7 Bearings: 14" Soft Maple N1° v 17.7' and 8" Spruce N47° w 16.3'			
13-Sec. 7 Bearings: 10" Cedar N58°N 7.6' and 12" Cedar N59°E 5.0			
SIGNED BY 3111y	lly D Suckles.	DATE	1/27/72
SURVEYOR'S MICHIGAN RE	GISTRATION NO. 8	867	(SEAL)
FOR STATE AND UNITED ST			
SIGNED BY	CHIEF OF SURVEY PARTY	DATE	
APPROVED AND SIGNED BY	M: CH: GÁN REG: STERED L	AND SURVEYOR DATE	(SEAL !

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971 DISTRIBUTED BY MICHIGAN SOCIETY OF REGISTERED LAND SURVEYORS

SURVEYOR'S MICHIGAN REGISTRATION NO.

The second secon

Form No. ML M735 DOUBLEDAY BROS & CO., KALAMAZOO, MICH.