

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co. Three Corners.

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. S. R. 7	C-4 14-Sec.7 7-Sec.7
2. PROPERTY CONTROLLING IN SECTION	7 T. 45 N. S. R. 7	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 11/13 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- C-4 ¼ Corner bet. Secs. 7-8, set by Wells surt, D.S. 1850.
 - 14-Sec.7 South 1/16 Corner, on Eastside, Sec. 7.
 - 7-Sec.7 North 1/16 Corner, on Eastside, Sec. 7.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- C-4 ¼ quarter Corner re-established midway and on line bet. Sec. Cors. Found no evidence of original corner. Found a 1" iron pipe N70°E 14.0' set by unknown persons.
 - 14-Sec.7 South 1/16 Cor. placed midway bet. Sec. Cor. to South and ¼ Cor. to North.
 - 7-Sec.7 North 1/16 Cor. placed midway bet. Sec. Cor. to North and ¼ Cor. to South.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- C-4 Placed 1" pipe with 4" aluminium cap at corner.
New Bearings:
12" Spruce N40°W 35.7' and 14" Spruce S74°W 59.9'
 - 14-Sec.7 Placed 4" Squared Post at corner.
Bearings:
Conc. R.O.W. Marker N78°W 85.5' and 7" W. Birch N4°E 58.1' and Center line N28 S40°E 34.0'
 - 7-Sec.7 Placed 1" pipe with 4" aluminium cap at corner.
Bearings: 1" pipe East 55.2' and 16" Aspen N52°E 26.3' and 14" Aspen S46°E 35.2'

SIGNED BY Billy D. Buckler DATE 11/27/72
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)