

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N.R. 7 W


Chippewa COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 31 and 32

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 10/28/60

WITNESSES TO CORNER... 10" Aspen (S 32 NBT) N 80° E 07 Links



7" Aspen (S 31 NBT) N 58° W 31 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by placing it on line and single proportionate measurement between Section corners 1 mile to east and west. Corner lies 41 links west of closing corner for Sections 5 and 6, T 44 N, R 7 W.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE July 14, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler