

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD

Luce and Chippewa COUNTY


T 45N R 7-SW

DESCRIPTION OF CORNER Section corner for Secs. 13, 24, 18, 19

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED 10/20/60 with Frank J. Bray

WITNESSES TO CORNER..... 14" cedar (S13 NBT) N75°W 24 links



13" cedar (S18 NBT) N45°E 70 links

7" Balsam (S24 NBT) S15°W 17 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one W. Pine stump (probable BT) bearing N60°E, 05 links. Found old blazes near corner. Squared and scribed 7" Cedar 05 links west of corner.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE

5/25/68

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68