

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 45N N.R. 7W


Chippewa COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 23-24-25-26

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 12-15-70

WITNESSES TO CORNER..... 7" Cedar (S24 NBT) N80°E 17.3'



9" Soft Maple (S23 NBT) N21°W 105.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner placed at a blazed Cedar, which is green and standing. Found numerous Cedar stump remains in vicinity but could identify none as original witnesses. Found possible line tree; a 36" W. Pine stump, 10 chs. east of this corner. Distance east and south to streams check well. Corner lies 75' north of log road.

SURVEYOR'S SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 1-21-71  
REGISTERED LAND SURVEYOR