

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45N N.R. 7W


Chippewa COUNTY

DESCRIPTION OF CORNER 1/4 Corner bet. Secs. 23-24

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 12-15-70

WITNESSES TO CORNER..... 12" Soft Maple (1/4 S NBT) S23°E 14.6'



12" Y. Birch (1/4 S NBT) N43°E 31.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at a large Hard Maple with old blazes on all four sides. Found blazed lines North, South and West from corner. Found no original witnesses. Position checks well with calls of notes and corner to south.

Corner lies 10' west of a logging trail.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 1-21-71
REGISTERED LAND SURVEYOR