

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45N N.R. 7W


Chippewa COUNTY

DESCRIPTION OF CORNER West 1/16 Cor. bet. Secs. 13-24

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 12-18-70

WITNESSES TO CORNER..... 13" Y. Birch (W 1/16 BT) N68°W 31.1'



10" Soft Maple (W 1/16 BT) N68°E 40.4'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner placed on line and midway between $\frac{1}{4}$ Cor. to East and Sec. Cor. to West. Found numerous blazes to East and West, on line, as well as a maple tree blazed on all four sides, close to the corner.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler DATE 1-21-71
REGISTERED LAND SURVEYOR