

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Chippewa

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---|-------------|
| 1. Public Land Survey | T <u>45N</u> R <u>7W</u> | <u>A8</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 17 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A8) Quarter corner common to Section 24 T45N-R08W and 19 T45N-R07W. 1840: Established by Wm A. Burt: North on East side Section 24...40.00 Set qr. Sect. post. Sugar 5 N4E 16, Sugar 11 S16W 15 ...80.00 Set post corner of Sections 13 & 24. 1960: The corner was reestablished and monumented by single proportionate measurement along the township line by Billy D. Buckler. Set 1" pipe with 4" brass cap. 8" Hard Maple N87E 59 links, 9" Hard Maple S48E 61.5 links (ref. LCRC 860A, Luce County Records).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A8) Found the 1960 monument projecting 1.5' above ground, in good condition and at substantial record bearing and distance from the two NBTs of record, both in good condition. I determined that the monument is S55W, 1.92' from the proportionate position between A7 and A9 as now monumented and accept same as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A8) Found 1" I.pipe with 4" brass MI Dept. of Conservation cap. Blazed, scribed, and set measuring nails in:
 10" Maple S87E 39.4' "1/4 S NBT" *
 12" Maple S50E 41.3' do *
 7" Maple S44W 10.3' do
 4" Maple N54W 10.35' do
 Bearings are magnetic. Distances are to nail with tag. * denotes 1960 NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/16/03

For the Michigan Department of Natural Resources, Office of Land and Facilities