

CHIPPEWA COUNTY REMONUMENTATION CORNER

MAR 27 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

Chippewa Located In: Corner Code #
(County)

1. Public Land Survey T46N R 2W (A-7) Same
T46N R 3W M-7 Corner
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

\$ 7.00 LAND CORNER
\$ 2.00 MSSR
29 FEB 96 9:28 A.M. RECEIPT# 462
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William L. Karr, in a field survey on Dec. 13, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	15	14	13							
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(A-7) Section Corner 18 & 19, T46N, R2W and Sections 13 & 24, T46N, R3W (M-7)

1840: Austin Burt set post

Fir 11" S73°W No distance given Fir 9" N63°W "do"

1941: Corner was established as part of a G.L.O. dependent resurvey. Set 6" diameter concrete monument with brass cap.


1977: J.H. Granger, P.S. 16041 found a concrete monument with G.L.O. brass cap. Corner was recorded in Liber 1, Page 251.

1987: N. Hill, P.S. 27447 (MDOT) found 5½" diameter concrete monument with G.L.O. brass cap. Corner was recorded in Liber 7, Page 80.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-7) This corner is being perpetuated as part of the Chippewa County Remonumentation program.

Found 5½" diameter concrete monument with G.L.O. brass cap as previously described along with many witnesses. Accepted corner position as found.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-7) Corner is a 5½" diameter concrete monument with G.L.O. brass cap 63.83 feet South of centerline and 3.0 feet East of centerline of Irish Line Road.

Witnesses: 3/4" Pipe w/Pk Nail S75°W 0.38'
Southerly Lip of SW Cor Conc Culvert N62°W 29.02'
Guy Pole S30°W 68.50'
Power Pole N13°E 136.48'
NW Cor Black Building S27°E 97.44'
Power Pole S19°E 66.95'



Signed by William L. Karr
Surveyor's Michigan License No. 27450

Date 12/13/95

NOTE: Bearings are compass bearings corrected for declination. Distances are to a nail in side of witness objects unless noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995