

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Chippewa County Remonumentation Corner**

**SURVEY & REMONUMENTATION**

APR 07 1998

For corners in

Chippewa

Located In:

Corner Code #

1. Public Land Survey

T 46N R 2W ✓

A-8 Same  
M-8 Corner

T 46N R 3W

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, William L. Karr, in a field survey on November 13, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

SECTION  
 \$7.00 LAND CORNER  
 \$2.00 MSSR  
 12 Mar 1998 12:36:00 PM Receipt #6527  
 RECEIVED FOR RECORD  
 CHIPPEWA COUNTY - STATE OF MICHIGAN  
 SHARON H. KENNEDY, REGISTER OF DEEDS  
 BOOK 10 PAGE 212  
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

(A-8) 1/4 Corner Common to Section 19, T.46 N., R.2 W., and Section 24, T.46 N., R.3 W.

1840 Austin Burt, D.S. set post in original survey. Witnesses: Spruce 14 S25°W 40  
 Fir 12 N50°W 15

1900 F. Brown, County Surveyor, ran West line Section 19; 2646' fence West; 5290' for mile.  
 1903 F. Brown, County Surveyor, ran West line Section 19; 5287' for mile.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-8) 1/4 Corner Common to Section 19, T.46 N., R.2 W., and Section 24, T.46 N., R.3 W.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found no evidence of original corner or subsequent restoration. Fence line to West noted in 1900 was not visible. Today's measurement for the mile was 5285.95'. Prorated the North 1/2 mile distance based on the 2646' measurement by Brown. Corner is on line between the Section corners. Distance North is 2645.47'; distance South is 2640.48'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-8) 1/4 Corner Common to Section 19, T.46 N., R.2 W., and Section 24, T.46 N., R.3 W.

Corner is a 3/4" x 24" iron with plastic Chippewa County Remonumentation Corner cap. Corner is 4' West of centerline of North-South Gravel road.

Witnesses: Power pole N33°E 90.53'  
 Spruce 6" N45°E 51.61'  
 3/4" x 24" capped pipe S42°W 48.71'  
 3/4" x 24" capped pipe N45°W 63.69'

Signed by William L. Karr

Date 12/29/97

Surveyor's Michigan License No. 27450

NOTE: All bearings are compass bearings corrected for declination (6°W). All distances are to a nail and tag in the side of witness object unless otherwise noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISED OCT., 1995