

MAY 28 1997

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1972,00 MSSR

Chippewa County Remonumentation Corner3/4/1997 2:13:14 PM

COMMISSION For corners in

Chippewa County Located in: Corner Code #

| 1. Public Land Survey   |   | T46N | R2W | D-9 |
|-------------------------|---|------|-----|-----|
| •                       |   | T    | R   | 2 0 |
|                         |   | Ť    | R   |     |
| -                       |   | Т    | R   |     |
| 2. Property Controlling | S | Τ    | R   |     |
| in Section              | S | Т    | R   |     |
| 3. Miscellaneous        | S | T    | R   |     |

RECEIVED FOR RECORD CHIPFEWA COUNTY - STATE OF NICHIGAN SHARON H. KENNEDY, REGISTER OF DEEDS

Receirt #294

26

BOOK 10 PAGE 68

3

6

8

9

10

12

18

32

Register of Deeds Stamp & File Number

4. Lot No.

, Recorded Plat


5. Private Claims

Property in Sec.

I, William L. Karr, in a field survey on December 16, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded

on this certificate.



## (D-9) 1/4 Corner Common to Sections 20 & 29, T. 46 N., R. 2 W.

1849 H. Mellen set sugar maple post for 1/4 corner in original survey.

Witnesses:

Cedar 12

S 80° E

12 lks

Hemlock 14

N 25° W

13 lks

1916 F.H. Brown, County Surveyor, surveyed portions of section 20, but does not note finding anything at the S. 1/4 corner or running the South line.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

## (D-9) 1/4 Corner Common to Sections 20 & 29, T. 46 N., R. 2 W.

This corner is being reestablished as part of the Chippewa County Remonumentation Program.

Found no evidence of original corner monument. Reestablished the corner mid-way and on-line between the section corners to the East and West. This position works well with the remains of an old hemlock stump, and the GLO distance to the stream to the West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

## (D-9) 1/4 Corner Common to Sections 20 & 29, T. 46 N., R. 2 W.

Corner is a 3/4" re-bar with plastic Chippewa County Remonumentation Cap. The corner falls halfway down an embankment of the stream to the West.

Witnesses:

LCRC 46N 02W D-09.doc

4" Maple N 50° E 1.31 6" Spruce S 62° E 12.93 12" Spruce S 09° E 7.97 4" Maple N 77° W 12.10 N 21° W 4" Maple 8.80

Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the otherwise noted.

Signed by

12-30-41

iess o<del>bj</del>éc<del>t u</del>niess SURVEYOR

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONA

REVISED OCT