

**SURVEY & REMONUMENTATION**

CHIPPEWA COUNTY REMONUMENTATION CORNER

\$9.00 LAND CORNER

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970 \$2.00 MSSR

MAY 28 1997

For corners in

3/4/1997 2:16:32 PM Receipt #294  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 70


Register of Deeds Stamp & File Number

Chippewa	located in:	Corner Code #
(County)		
1. Public Land Survey	T46N R 2W	E-2
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, William L. Karr, in a field survey on Dec. 17, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.



A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5	●	4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		16		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration.  
 (E-2) 1/4 Corner Common to Sections 4 & 5, T.46 N., R.2 W.  
 1849: H. Mellen set post Hemlock 16 S32°E 11 Hemlock 10 N68°W 32  
 19??: Supervisor's Plat of the Village of Brimley.  
 1954: G.D. Henning, P.S. 2240 was hired by the Township to survey the line between Sections 4 & 5. There was considerable controversy over the existing position of 1/4 corner 4 & 5. Henning did an extensive survey and located Section corners to the East-West and South. He also notes his position for the Section line is consistent with a number of building lines South of the corner in the Plat of the (OVER)
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.  
 (E-2) This Corner is being perpetuated as part of the Chippewa County Remonumentation Program.  
 Found no evidence of original corner. Found the brass cap in the bridge deck as recorded in 1980. Distances East, West and South to corners match Henning's 1954 survey. A number of old building faces South of the corner fit the R.O.W. line as constructed off of the Henning line. Accepted Henning's corner as previously recorded and established (1) new witness.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.  
 (E-2) Corner is a Chippewa County brass cap at the West end of bridge, 12.4' East of the extension of the centerline of M-221.

Witnesses:	Southwesterly corner concrete bldg.	N48°E	200.22'
	Power pole	S33°E	155.61' (existing)
	Power pole (#E241/250)	S17°W	133.44' (existing)
	Fire hydrant (chisled "x" - N.E. bolt)	N68°W	104.89' (existing)

Signed by William L. Karr  
 Surveyor's Michigan License No. 27450

Date 12-30-96



NOTE: All bearings are compass bearings corrected for declination. All distances are to a nail in side of witness objects unless noted.

PART OF SECTION A

1954 (continued):

Village of Brimley. His survey and accompanying notes are on file in the County Surveyor's office. His location for the 1/4 corner is 19.00' East of the generally accepted position.

1974: Neree Alix, P.S. 6254 records Assessor's Plat of Goldade Acres in Liber 9 of Plats, Page 22. The Plat shows both corner positions from 1954 Henning survey.

1974: N.C. Jones, P.S. 2934 M.D.O.T. Surveyor records the Easterly corner set by Henning. Corner is recorded in Liber 1, Page 108 of the Chippewa County Corner Records.

1977: Bridge across Waiska River is re-built.

1980: J.H. Granger sets brass cap (flush) in concrete roadway on new bridge at Henning's position (Jones position also).

1990's: Numerous surveys in Section 4 & 5 use the Henning position.

SURVEY &  
REMONUMENTATION

BOOK 10 PAGE 71

MAY 28 1997

COMMISSION