

MAY 28 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
 Chippewa County Remonumentation Corner

For corners in

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T46N R2W	E-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

\$7.00 LAND CORNER

\$2.00 MSSR

3/4/1997 2:20:46 PM Receipt #294

RECEIVED FOR RECORD

CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 76

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on December 17, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E-8) 1/4 Corner Common to Sections 20 & 21, T. 46 N., R. 2 W.

1849 H. Mellen set cedar 1/4 section post in original survey.
 Witnesses: Cedar 12 East 18 lks
 Cedar 7 N 27° W 22 lks

1916 F.H. Brown in section drawing book in County Surveyors Office, reestablished corner by running 200' South from the Northeast corner of section 20. Brown's notes show that the Southeast corner of section 20 is lost.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-8) 1/4 Corner Common to Sections 20 & 21, T. 46 N., R. 2 W.

This corner is being reestablished as part of the Chippewa County Remonumentation Program.

Could find no evidence of the original corner or of the post set by Brown in 1916. Reestablished the corner mid-way between the section corners to the North and South, using an old roadbed for East-West position. Distance North and South to section corners is 2611.17'; Corner falls 10.7' West of a straight line between the section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-8) 1/4 Corner Common to Sections 20 & 21, T. 46 N., R. 2 W.

Corner is a 1/2" iron with plastic cap no. 27450. Corner falls in the centerline of an old roadbed and 12' West of a North-South ditch.

Witnesses: Wood Post N 61° E 30.83'
 13" Balsam Fir S 09° E 101.21'
 8" Balsam Fir S 12° W 114.15'
 1/2" Iron N 45° W 45.00'

Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by William L. Karr

Date 12-30-96

Surveyor's Michigan License No. 27450

